

10-22

4-032266

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-137-20,393 00-00

NE NE NW /4 SEC. 28, 05, 22 W
4950 feet from S section line
2970 feet from E section line

Operator license# 4767

Lease: White-28A Well # 1

Operator: Ritchie Exploration, Inc.

County: Norton 119.28

Address: P.O. Box 783188
Wichita, Kansas 67278-3188

Well total depth 3670 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 258 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 22 Month: October Year: 1997

Plugging proposal received from: Pete

Company: Ritchie Exploration, Inc. Phone: -

Were: Order 210 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All , Part , None

Completed: Hour: 9:30 A.M., Day: 22 Month: October, Year: 1997

Actual plugging report: 8 5/8" set at 258' w/200 sxs cwc. 4 1/2" set at 3666' w/150 sxs. PBD 3604'. Port collar at 1823' w/290 sxs cwc. Prod. Perfs. 3600' - 3632'. Squeezed 4 1/2" w/200 sxs cement blend to Max. P.S.I. 800#. Held. Cement at surface in 8 5/8". Plug complete. Tested to 500#.

Remarks:
Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: _____ GL

I did did not observe the plugging

Carl Goodrow
(agent)

INVOICED
DATE 11-4-97
INV. NO. 49429