

8-22

6-050121

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-137-20,392 *0000*
S2 S2 S2 /4 SEC. 28, 5 S, 22 W
330 feet from S section line
2540 feet from E section line

Operator license# 4767 Lease White 28B well # 2

Operator: Ritchie Exploration, Inc. County Norton

Address: 125 N. Market, Suite 1000 Well total depth 3735 feet
Wichita, Kansas 67202 Conductor Pipe: inch @ feet
Surface pipe 8 5/8 Inch @ 240 feet

121.38

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Murfin Drilling License# 30606

Address: Wichita, Kansas

Company to plug at: Hour: pm Day: 22 Month: August Year: 1993

Plugging proposal received from: Lloyd Delett

Company: Murfin Drilling phone:

Were: **Spot plugs through drill pipe w/ heavy mud between all plugs.**

1st plug @ 1940 feet with 25 sacks Rat hole: 15 sacks

2nd plug @ 1145 feet " 100 " Mousehole: NA sacks

3rd plug @ 300 feet " 40 "

4th plug @ 40 feet " wiper plug & 10sx

Plugging Proposal Received by: Bruce D. Basye

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 12:15 PM, Day: 22, Month: August, Year: 1993

Actual plugging report: Hole reported plugged as above.

Order 190 sx 60/40 pozmix w/ 6% gel and 2sx celloflake or flowcel.

Remarks: Elevation: 2291 GL, Anhydrite depth: 1925 - 1957 feet

Did not penetrate Arbuckle, cemented by Allied

I did[] / did not[X] observe the plugging.

RECEIVED
STATE CORPORATION COMMISSION

SEP 02 1993

CONSERVATION DIVISION
Wichita, Kansas

Bruce D. Basye Geologist
(agent)

Form CP-2/3

INVOICED

DATE SEP 02 1993

INV. NO. 38548

HO