

2-1

19
R

6 - 060293

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-137-20,378 00-00

SWSEW /4 SEC. 28, 05 S. 22 W
330 feet from S section line
3630 feet from E section line

Operator license# 47676 Lease White 28B well # 1

Operator: Ritchie Exploration Inc. County Norton

Address: 125 N. Market #1000 Well total depth 3805' feet 123.66
Wichita, Ks. 67202 Conductor Pipe: inch @ feet
Surface pipe 8 5/8 inch @ feet

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Murfin License# 30606

Address: Wichita, Ks.

Company to plug at: Hour: 12:30PM Day: 01 Month: February Year: 92

Plugging proposal received from: Lloyd Delett

Company: Murfin phone:

Arb. not reached.

Were: **Spot plugs through drill pipe w/ heavy mud between all plugs.**

Order 200 sks cement 60/40 poz 6% gel and 1/4 lb. f.c. per sk.

1st plug @ 2010 feet with 25 sacks Rat hole: 15 sacks

2nd plug @ 1215 feet " 100 " Mousehole 10 sks

3rd plug @ 300 feet " 40 " Anhy 1991-2021

4th plug @ 40 feet " 10 " Dakota 914-1214

5th plug @ feet " wiper plug & 10sx

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 12:30PM, Day: 01, Month: February, Year: 92

Actual plugging report: Plugged as stated above.

Remarks: Elevation: 2364 GL, Anhydrite depth: - feet

Anhy. plug: YES Dakota plug: Bottom hole plug in place: NO

Plugged through drill pipe: YES

Did penetrate Arbuckle, cemented by Allied Cement

I did[] / did not[X] observe the plugging.

DATE 2-21-92

INV. NO. 34623

Herb Deines
Herb Deines

(agent)

Form CP-2/3

File 3

RECEIVED
STATE CORPORATION COMMISSION
FEB 12 1992
CONSERVATION DIVISION
WICHITA, KANSAS

2-12-92