

6 070333

API NUMBER 15-137-20, 354-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE-SE-SE, SEC. 5, T. 5 S. R. 24 W.

330 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5313

Lease Name WYRELL Well # "Q" #1

Operator: F. & M. OIL CO., INC.

County NORTON 154.34

Name & Address 422 UNION CENTER

Well Total Depth 4749 3749 feet

WICHITA, KANS.

Conductor Pipe: Size 0 feet

67202

Surface Casing: Size 8 5/8 feet 259

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated TAG # 183

Plugging Contractor ABERCROMBIE DRILLING INC. License Number 3422

Address WICHITA, KANSAS. 67202

Company to plug at: Hour: 3:30 PM Day: 10 TH Month: MARCH Year: 1985

Plugging proposal received from WILBER DRILLING

(company name) ABERCROMBIE DRILLING INC. 24% 3% (phone 316-262-2636)

were: 8 5/8" - 259 ESP CUL #180 SK CLASS A GEL - CH-AL (BY HALLIBURTON)

ORDER 200 SK 50/150 Pozmix GEL - CH-AL-1 SK CELLO FLAME AND 8 5/8" PLUG

SPOT WITH DRILL STEM, RECONDITION HOLE (MUD VIS 45) MUD BETWEEN ALL PLUGS.

NO CIRCULATION PROBLEMS, MUD COND. Weight 9.4, VIS 43, CHLORIDES 2000

KC. WELL, NO ARBUCKLE, ELV. 2414, ANH. 2009,

Plugging Proposal Received by Marian Schmidt
DOIC (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 3:15 PM Day: 10 TH Month: MARCH Year: 1985

ACTUAL PLUGGING REPORT ORDERED 200 SK 50/150 Pozmix GEL - CH-AL - 8 5/8" PLUG, 1 FLAME SK CELLO

SPOTTED WITH DRILL STEM, RECONDITIONED HOLE, HEAVY MUD BETWEEN ALL PLUGS

1st PLUG @ 2020 FT #30 SK CNT, 2nd PLUG @ 1220 FT #100 SK CNT #1 Cello, #1 FLAME

3rd PLUG @ 270 FT #50 SK CNT, 4th PLUG ^{SAND BRIDGE} @ 40 FT #20 SK CNT

10 SK IN ENT HOLE (CIRCULATE)

STATE CORPORATION COMMISSION

CEMENTED BY ALLIED CNT.

MAR 18 1985 3-18-85

Remarks: _____ (If additional description is necessary, use BACK of this form.)

I did (did not) observe this plugging.

DATE 3-19-85

Signed Marian Schmidt
DOIC (TECHNICIAN) 3-15-85 15

INV. NO. 7391

3-10