

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-119-20389-00-00
Spot: SWNW Sec/Twnshp/Rge: 36-31S-28W
1980 feet from N Section Line, 660 feet from W Section Line
Lease Name: EDWARDS Well #: 1
County: MEADE Total Vertical Depth: 5660 feet

Operator License No.: 3062
Op Name: QUESTA ENERGY CORPORATION
Address: PO BOX 19297 3601 S. GEORGIA
AMARILLO, TX 79114

CIBP Size: feet: 5250 WITH 2 SX CMT
PROD Size: 4.5 feet: 5397 WITH 150 SX CMT
SURF Size: 8.625 feet: 1414 WITH 685 SX CMT

#18328

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/16/2004 11:35 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: SERGIO ESTRADA Company: BADGER RESOURCES INC Phone: _____

Proposed Plugging Method: CIBP @ 5250' WITH 2 SX CMT. PLUG AT 1430' WITH 40 SX CMT. PLUG AT 500' WITH 40 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/16/2004 1:30 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

CIBP @ 5250' WITH 2 SX CMT ON TOP. 1ST PLUG CASING LEAK AT 4059' SPOT 50 SX CMT. 2ND PLUG PULL TO 1430' & SPOT 50 SX CMT. 3RD PLUG PULL TO 514' & SPOT 50 SX CMT. 4TH PLUG FLUID AT 200' SPOT 35 SX CMT. STAYED FULL.

Perfs:


Top	Bot	Thru	Comments
5302	5308		

RECEIVED
DEC 27 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ORR ENTERPRISES. RECOVERED 2739' OF 4 1/2" CASING.

Plugged through: TBG

District: 01



Signed _____

(TECHNICIAN)

INVOICED
DATE 12-29-04
INV. NO. 2005060981

Form CP-2/3