

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-175-20071-00-00  
Spot: SWSWNE Sec/Twnshp/Rge: 18-33S-33W  
1250 feet from N Section Line, 1250 feet from E Section Line  
Lease Name: FREEMAN Well #: 1  
County: SEWARD Total Vertical Depth: 6230 feet

Operator License No.: 6120  
Op Name: CABOT OIL & GAS CORPORATION  
Address: 600 17TH ST., SUITE 900 NORTH  
DENVER, CO 80202

CIBP Size: feet: 4380 WITH 2 SX CMT  
MSCC Size: feet: 4713 WITH 140 SX CMT  
PROD Size: 5.5 feet: 5818 WITH 150 SX CMT  
SURF Size: 8.625 feet: 1622 WITH 550 SX CMT

48  
\$202

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/17/2004 9:00 AM  
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.  
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PLUG AT 1650' WITH 50 SX CMT. PLUG AT 720' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

RECEIVED  
DEC 29 2004

Plugging Proposal Received By: STEVE DURRANT  
Date/Time Plugging Completed: 12/20/2004 5:00 PM

WitnessType: COMPLETE (100%)  
KCC Agent: KEN JEHLIK

KCC WICHITA

Actual Plugging Report:

PBTD 5749'. CIBP SET @ 4380' WITH 2 SX CMT. 1ST PLUG AT 1650' WITH 50 SX CMT. 2ND PLUG AT 720' WITH 30 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT. GOOD CIRCULATION ON ALL PLUGS.


Perfs:

Top	Bot	Thru	Comments
5692	5696		
4409	4412		

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 2477' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

*[Handwritten Signature]*

(TECHNICIAN)

INVOICED

DATE 12-29-04

INV. NO. 2005060487

Form CP-215