

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-20379-00-00
Spot: NWNE Sec/Twnshp/Rge: 21-28S-34W
4620 feet from S Section Line, 1980 feet from E Section Line
Lease Name: LUCAS WAYNE Well #: 4
County: HASKELL Total Vertical Depth: 5634 feet

Operator License No.: 33002
Op Name: WESTPORT OIL AND GAS COMPANY L
Address: 5735 PINELAND, SUITE 300
DALLAS, TX 75231

CIBP Size: feet: 4560
CIBP Size: feet: 4575 WITH 2 SX CMT
CIBP Size: feet: 4690 WITH 2 SX CMT
CIBP Size: feet: 4800 WITH 2 SX CMT
CIBP Size: feet: 5250 WITH 2 SX CMT
PROD Size: 5.5 feet: 5633 WITH 635 SX CMT
SURF Size: 9.625 feet: 1897 WITH 710 SX CMT

183^W

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/14/2004 3:00 PM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: ROGER MORTHCUTT Company: WESTPORT OIL & GAS Phone: (214) 692-1800

Proposed Plugging Method: PUMP 300# HULLS & 25 SX CMT. PLUG AT 1920' WITH 60 SX CMT. PLUG AT 750' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/15/2004 10:00 AM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 4560'. PUMP 300# HULLS WITH 25 SX CMT. DISPLACE TO BOTTOM WITH MUD. LOAD 5 1/2" & PRESSURE TO 500 PSIG. 1ST PLUG AT 1920'. LOAD HOLE WITH MUD & PUMP 60 SX CMT. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE TO 750'. LOAD HOLE & PUMP 40 SX CMT. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE TO 40'. LOAD HOLE & PUMP 12 SX CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
5326	5334		
4863			
4722			
4618	4622		
4375	4387		

INVOICED
DATE 12-29-04
NO. 2005060984

RECEIVED
DEC 27 2004
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 1920' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED
DEC 21 2004
KCC Dodge City

Signed

Jim Holland
(TECHNICIAN)

[Handwritten signature]