

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-21911-00-00  
Spot: NESE Sec/Twnshp/Rge: 7-28S-8W  
2015 feet from S Section Line, 710 feet from E Section Line  
Lease Name: TRUDY Well #: 1  
County: KINGMAN Total Vertical Depth: 4320 feet

Operator License No.: 31881  
Op Name: MCGINNESS OIL COMPANY OF KANS  
Address: 150 N. MAIN, STE 1026  
WICHITA, KS 67202

PROD Size: 4.5 feet: 4295 225 SX CMT  
SURF Size: 8.625 feet: 265 190 SX CMT

# 140 40

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/16/2004 11:00 AM  
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.  
Proposal Rcvd. from: DOUGLAS H MCGINNESS Company: MCGINNESS OIL COMPANY OF K Phone: (316) 267-6065

Proposed  
Plugging  
Method:

CIBP 3266' w/ 4 sxs common; 1200' w/ 35 sxs; 750' w/ 35 sxs; and 315' - 0'.

RECEIVED  
KCC DISTRICT #2  
DEC 20 2004  
WICHITA, KS

Plugging Proposal Received By: JACK LUTHI Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/16/2004 4:30 PM KCC Agent: JACK LUTHI

Actual Plugging Report:

Set CIBP at 3266' with 4 sacks of common cement. Shot 5-1/2" casing off at 2428'. Pulled to 1200' and pumped 35 sacks of cement. Pulled to 750' and pumped 35 sacks of cement. Pulled to 315' and circulated cement to surface.

Allied Cement

60/40 posmix with 4% gel.

Perfs:

Top	Bot	Thru	Comments
3970	3971		
3969	3974		
3910	3972		
3720	3723		

RECEIVED  
DEC 27 2004  
KCC WICHITA

Remarks:

Plugged through: CSG

District: 02

Signed Jack Luthi  
(TECHNICIAN)

INVOICED

DATE 12-29-04  
REV. NO. 2005060977