

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-199-20244-00-01
Spot: SWSWNW Sec/Twnshp/Rge: 20-15S-41W
2970 feet from S Section Line, 4950 feet from E Section Line
Lease Name: WEIS Well #: 1
County: WALLACE Total Vertical Depth: 5198 feet

Operator License No.: 8541
Op Name: PETEX, INC.
Address: 4175 S. FR 193
ROGERSVILLE, MO 65742

PROD Size: 5.5 feet: 5194 150 SX CMT
SURF Size: 8.625 feet: 359 265 SX CMT

1/68 94

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/13/2004 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: TOM LARSON Company: LARSON ENGINEERING, INC. Phone: (720) 653-7368

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 10% gel - 500# hulls.
Plug through tubing and casing.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/13/2004 3:30 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface pipe set at 359' w/265 sxs cement.
5 1/2" production casing set at 5194' w/150 sxs cement.
DV Tool at 2741' with 300 sxs Midcon II cement. PBTD 5150'.
Junk in hole from 4500' to 5145'. Tubing stuck in 5 1/2" casing at approximately 4500'.
Pulled rods and pump out of tubing.
Connected to tubing - pumped 40 sxs cement.
Displaced tubing with 26 barrels water.
Cut tubing at 4500'.
Pulled tubing to 4470' - pumped 29 sxs gel - cement in returns.
Pumped 40 sxs cement with 50# hulls.
Pulled tubing - pumped 150 sxs cement from surface.
Max. P.S.I. 600#. S.I.P. 0#.
Connected to 8 5/8" surface casing - pumped 5 sxs cement
Max. P.S.I. 200#. Braden head ruptured.

Perfs:

Top	Bot	Thru	Comments
5005	5008		

Remarks: ALLIED CEMENTING COMPANY-TICKET #19565.

Plugged through: TBG

District: 04

100

Signed Darrel Dipman
(TECHNICIAN)

INVOICED
DATE 12.29.04
INV. NO. 2005060980

DEC 14 2004

~~DATE~~
~~NO. 18~~
WADICEN

PETEX INC
SPRINGFIELD MO 65804

20-15S-41W
SW SW NW

#1 WEIS

site: 9 S & 2-1/2 E OF WESKAN KS	dy: WALLACE	API 15-199-20244
contr: MURFIN DRILLING # 14	field: MOUNT SUNFLOWER NE	
well:	EXT (1/8 NE)	
fr date 12/04/96	spc date 12/12/96	drig comp 12/26/96
	card issued 10/06/97	last revised 10/06/97

ELV: 3812 GL
tops.....depth/datum
ERTD.....5300 -1488
NO TOPS RPTD

IP status:
OIL, MRW, INTV NA, 06/01/97
CSG: SP 350 (ALT 2), PROD CSG NA
TRGT ZN: MRW (OIL), PTD 5300 (MISS), MICT - CO, PF
(MRW SD) INTV NA, SO, POP, OIL WELL (POTENTIAL
NOT RPTD), 6/1/97 - TIGHT HOLE - NO OTHER INFO
AVAILABLE - TEMP COMP 10/6/97

COPYRIGHT 1997
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS