

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-21854-00-00
Spot: SWSE Sec/Twnshp/Rge: 28-16S-28W
660 feet from S Section Line, 1980 feet from E Section Line
Lease Name: FULLMER Well #: 1
County: LANE Total Vertical Depth: 4670 feet

Operator License No.: 6569
Op Name: SCHMITT, CARMEN, INC.
Address: PO BOX 47
GREAT BEND, KS 67530

SURF Size: 8.625 feet: 209

#15178

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 12/17/2004 12:00 AM
Plug Co. License No.: 5184 Plug Co. Name: SHIELDS OIL PRODUCERS INC
Proposal Rcvd. from: BURT Company: SHIELDS OIL PRODUCERS INC Phone: (785) 483-3141

Proposed Plugging Method: 1ST PLUG AT 2212' WITH 50 SX CMT. 2ND PLUG AT 1350' WITH 80 SX CMT. 3RD PLUG AT 675' WITH 50 SX CMT. 4TH PLUG AT 240' WITH 40 SX CMT. 5TH PLUG AT 40' WITH 10 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: NONE
Date/Time Plugging Completed: 12/17/2004 4:00 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

Perfs:


1ST PLUG AT 2212' WITH 50 SX CMT. 2ND PLUG AT 1350' WITH 80 SX CMT. 3RD PLUG AT 675' WITH 50 SX CMT. 4TH PLUG AT 240' WITH 40 SX CMT. 5TH PLUG AT 40' WITH 10 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

RECEIVED
DEC 27 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01



Signed

Stephen J. Pfeifer
(TECHNICIAN)

INVOICED

DATE 12-29-04

INVOICE NO. 2005060982

Form CP-23