

15-039-00507-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Decatur County, Sec. 15 Twp. 5 Rge. (E) 27 (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE SE SE

Lease Owner R. W. Shields

Lease Name Martin Feeley Well No. 1

Office Address

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed Nov. 9 19 53

Application for plugging filed Jan. 1 19 54

Application for plugging approved verbal approval in Nov. but oper stopped by storm.

Plugging commenced Jan. 2 19 54

Plugging completed Jan. 7 19 54

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3900 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
		-0-	222	8 5/8"	222	-0-
		-0-	3898	5 1/2"	3898	Approx. 2650'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set. Filled hole with sand to 3650'.

Dumped 5 sacks of cement in bottom of hole. Shot pipe off at 2651'. Pulled pipe and mudded hole to 200'. Set rock bridge and dumped 20 sacks of cement at 200'. Finished mudding hole and dumped 10 sacks of cement at base of cellar.

1-27-54

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to R. W. Shields
Address 308 Rule Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Reno, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bert Seff
PP H of Hutchinson, Mo.
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of January, 19 54

My commission expires Aug. 12 1957 Notary Public.

PLUGGING
FILE SEC 15 T 5 R 27W
BOOK PAGE 142 LINE 45