

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84
RECEIVED
STATE CORPORATION COMMISSION
03-15-1989
MAR 15 1989

WELL PLUGGING APPLICATION FORM
(File One Copy)

CONSERVATION DIVISION
Wichita, Kansas

API NUMBER 15-137-20333-00-00 (of this well) 10/89
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Maxus Exploration Company OPERATORS LICENSE NO. 9123

ADDRESS P. O. Box 400, Amarillo, TX 79188-0001 PHONE # (806) 371-4582

LEASE (FARM) Marion Goldsby WELL NO. 1 WELL LOCATION N/2 SE NE COUNTY Norton

SEC. 10 TWP. 5S RGE. 25 ~~W~~ or (W) TOTAL DEPTH 3,744' PLUG BACK TO 3,605'

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL DOCKET NO. CD 18116

SURFACE CASING SIZE 8 5/8" SET AT 299' CEMENTED WITH 225 SACKS

CASING SIZE 5 1/2" SET AT 3,854' CEMENTED WITH 200 SACKS

3728'-3734', CIBP @ 3700'; 3160'-3164', CIBP @ 3605',
PERFORATED AT 3568'-3572', 3582'-3590'

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL A port collar was placed at 2,098' and cement
was circulated from 2,098' to surface (350 sx HLC). The 4 1/2"-8 5/8" annulus will be pressure
tested with cement. The 4 1/2" casing "Bull Squeezed" with 300 sx 60-40 Poz cement w/6% gel and
5 sx of hulls. (If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN Upon approval of the KCC

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

James L. Skees, Production Engineer PHONE # (806) 371-4582

ADDRESS P. O. Box 400, Amarillo, TX 79188-0001

PLUGGING CONTRACTOR Halliburton Services LICENSE NO. 5287

ADDRESS P. O. Box 47, Oberlin, KS 67749 PHONE # (913) 475-2228

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: James L. Skees
(Operator or Agent) James Skees

DATE: March 13, 1989

④



15-137-20333-00-00

Kansas Corporation Commission

MIKE HAYDEN	GOVERNOR
KEITH R. HENLEY	CHAIRMAN
RICH KOWALEWSKI	COMMISSIONER
MARGALEE WRIGHT	COMMISSIONER
JUDITH McCONNELL	EXECUTIVE DIRECTOR
FRANK A. CARO, JR.	GENERAL COUNSEL

CONSERVATION DIVISION
 SHARI M. FEIST, DIRECTOR
 200 Colorado Derby Bldg.
 202 W. 1st Street
 Wichita, KS 67202-1286
 (316) 263-3238

THIS NOTICE
JUN 17 1989
EXPIRES

March 17, 1989

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

Maxus Exploration Company
 P. O. Box 400
 Amarillo, TX 79188-0001

Marion Goldsby #1
 N/2 SE NE
 Sec. 10-05S-25W
 Norton County

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist Albrecht
 Shari Feist Albrecht
 Director

District: #4 2301 E. 13th

 Hays, KS 67601

 (913) 628-1200

