

7-20

4-100529

TO:

API number: 15- 137-20,403- 00-00

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, ROOM #2078
WICHITA, KANSAS 67202-3802

S2 NW SE SW /4 SEC: 21-05-22 W
890 Feet from S (N/S) Line
1650 Feet from W (E/W) Line

Operator License 04767

LEASE: B. Griffey WELL # 1

Operator: Ritchie Exploration, Inc.

County: NORTON 122.53

Address: P.O. Box 783188
Wichita, Kans. 67278

Well total Dept 3770 feet
Conductor Pipe _____ inch @ _____ feet
Surface pipe 8 5/8 inch @ 253 feet

Aband. Oil Wel _____ Gas Well _____ Input Wel _____ SWD: _____ D & A: X

Pluggin contractor: White & Ellis Drilling, Inc. License#: 05420

Address: _____

Company to plug at: _____ Hour: _____ Day: _____ Month: _____ Year: _____

Plugging proposal received from Judy

Company: White & Ellis Drilling, Inc. Phone: _____

Were:

- 1st plug @ 1960' with 25 sx
- 2nd plug @ 1190' with 100 sx
- 3rd plug @ 300' with 40 sx
- 4th plug @ 40' with a wiper plug and 10sx
- Rat hole - 15 sx

Plugging proposal recived by David Wann

Pluggings operations attended by agent? All [], Part [], None [X]

Completed Hour: 11:00 PM Day: 20, Month: July Year: 1997

Actual plugging report:

Hole reported plugged as above.

Order 190 sacks 60/40 pozmix w/ 6% gell and 2 sacks of celloflake.

Remarks: Elevation: 2339 GL, Anhydrite top: 1960 feet Anhy. plug: Y

Dakota plug: Y Bottom plug in plac N

Plugged through drill pip Y

Arbuckle top Cemented by: Allied Cementing.

I did [] did NOT [X] observe the plugging

7-24-97
David Wann
P.I.R.T. III
(agent)

INVOICED

DATE 7-25-97

INV. NO. 48675