

6-100456

8-27

79
R

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-137-20,384-00-00
SW SW NW /4 SEC. 21, 05 S, 22 W
2970 feet from S section line
4950 feet from E section line

Operator license# 4767 Lease White 21B well # 1

Operator: Ritchie Exploration, Inc. County Norton

Address: 125 North Market, # 1000 Well total depth 3670 feet 119.27
Wichita, Kansas 67202
Conductor Pipe: inch @ feet
Surface pipe 8 5/8 Inch @ 208 feet

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Murfin Drilling License# 30606

Address: Wichita, Kansas

Company to plug at: Hour: ?? Day: Month: Year:

Plugging proposal received from: Lloyd Delette

Company: Murfin Drilling phone:

Were: **Spot plugs through drill pipe w/ heavy mud between all plugs.**

1st plug @ 1875 feet with 25 sacks Rat hole: 15 sacks
2nd plug @ 1090 feet " 100 " Mousehole: sacks
3rd plug @ 250 feet " 40 "
4th plug @ 40 feet " Wiper plug & 10 sx.

5th plug @ feet "

Plugging Proposal Received by: David K. Wann

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 4:00 pm, Day: 27, Month: August, Year: 1992

Actual plugging report: Hole reported plugged as above.

Order 190 sx 60/40 pozmix w/ 6% gel and 2 sx celloflake or flowcel.

RECEIVED
STATE CORPORATION COMMISSION
SEP 28 1992
9-28-92
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Elevation: 2241 GL, Anhydrite depth: 1872 - 1904 feet
Anhy. plug: YES Dakota plug: YES Bottom hole plug in place: YES
Plugged through drill pipe: YES
Did NOT penetrate Arbuckle, cemented by Allied Cementing.

I did , did not X observe the plugging.

David K. Wann
David K. Wann P.I.R.T. II
(agent)

INVOICED
DATE 9-30-92
INV. NO. 36274