

4-031622

12- -91

212
R

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-137-20282-00-00

NE SW NE /4 SEC. 15, 05 S, 22 W
3630 feet from S section line
1650 feet from E section line

Operator license# 5252

Lease Riemann well # 1

Operator: R.P. Nixon Operations Inc.

County Norton

Address: 207 West 12th Street
Hays, Kansas 67601

Well total depth 3600 feet PBTB 3487'
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 282 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Jay-Lan Corporation License# 5128

Address: 207 West 12th Street, Hays, Kansas 67601

Company to plug at: Hour: Day: Month: December Year: 91

Plugging proposal received from: Paul Nixon

Company: R.P. Nixon Operations Inc. Phone:

Were: Order 350 sx. 65/35 pozmix - 10% gel. - 500# hulls.
B.J. Services. Tracy Water Trucks.
Shots @ 1680' and 1000'. Casing open to TD with wireline.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 6:00P.M., Day: 4, Month: December, Year: 91

Actual plugging report: 8 5/8" @ 282' w/185 sks. 5 1/2" @ 3581 w/150
sk. Top perf. @3276'. Squeezed 5 1/2" w/330 with cement blend -
500# hulls mixed in. Squeezed backside w/10 sks. cement blend.
Stretch on 5 1/2 was only 1/2". Had to cut slips out to release.
Max. pressure on 5 1/2" - 1000 P.S.I. Shut in @ 700 P.S.I.
Max. pressure on backside - 500 P.S.I. Shut in @ 500 P.S.I.

DEC 30 1991

Remarks:

I did X / did not [] observe the plugging. Carl Goodrow

DATE 1-10-92
INV. NO. 34303

John S.

(agent)