

4-041840

15-137-00596-00-00

API Number: 15- - 05-12-42

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

NE NE SE /4 SEC. 36 , 05 S, 21 W
2310 feet from S section line
330 feet from E section line

Operator license# 5447

Lease: Kitzke Well # 1

Operator: OXY USA, Inc.

County: Norton 117.26

Address: P.O. Box 300
Tulsa, Oklahoma 74102-0300

Well total depth 3608 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 152 feet
w/125 sxs.cmt.

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Halliburton Cementing, Inc. License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: 3:00 P.M. Day: 7 Month: November Year 1996

Plugging proposal received from: Jim Nowell

Company: OXY USA, Inc. Phone: 918-561-3564

Were: 5 1/2" casing set at 3602' w/100 sxs.

Open hole.
PPTD 3606'.

01-10-1997

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 5:15 P.M., Day: 7, Month: November, Year: 1996

Actual plugging report: Dug out casing and orange peeled 5 1/2" to 8 5/8" casing. Install 2" riser to surface. Rigged up H.L.S. & perf at 1100' and 1750' with 2 spf. MIRU Murfin Drilling, RIH with 2 3/8" tubing. Open ended to 3580'. Pumped 65 sxs MIDCON 2 with 2% CC and 300# cottonseed hulls. Pulled 48 jts. to 2000'. Pumped 65 sxs cement & 200# hulls. Pulled tubing to 600'. Pumped 40 sxs cement and circulated to surface. POOH with rest of tubing. Hooked up to 5 1/2" casing and pumped 30 sxs cement. Max. P.S.I. 400#. Closed in 5 1/2". Hooked up to 8 5/8" casing and pumped 60 sxs MIDCON 2 cement with 2% CC and 100# hulls. Max. P.S.I. 300#. S.I.P. 250#. Total cement used 260 sxs.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD X BAD
Bottom plug(in place): YES X, CALC, NO
Plugged through TUBING X, CASING
Anhy.plug: YES X NO
Dakota plug: YES X, NO
Elevation: 2180 K.B.

I did [X] / did not [] observe the plugging.

Dennis L. Hamel
(agent)

Form CP-2/3

INVOICED

DATE JAN 10 1997

INV. NO. 47325