

15-137-00735-00-00

4-041673

4-27

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 S. MARKET, ROOM #2078  
WICHITA, KANSAS 67202

API number: 15- - 4-12-46

NE SE NE /4 SEC. 36, 05 S, 21 W  
3630 feet from S section line  
330 feet from E section line

Operator license# 5447

Lease Veeh 'A' well # 4

Operator: OXY USA, Inc.

County Norton 117.91

Address: 110 S. Main  
Suite #800  
Wichita, Kansas 67202

Well total depth 3628 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 206 feet  
w/125 sxs.

Aband. oil well X, Gas well    , Input well    , SWD    , D & A    

Plugging contractor: Halliburton Cementing License#    

Address: Hays, Kansas 67601

Company to plug at: Hour: 9:00A.M. Day: 27 Month: April Year: 95

Plugging proposal received from: Jim Nowell

Company: OXY USA, Inc. Phone:    

Were: 5 1/2" casing set at 3620' w/150 sxs. cement.  
Anhy. at 1796' - Dakota at 1096'. Perfs. at 3625' - 3628'.  
Ordered 400 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls.

STATE CORPORATION COMMISSION

Plugging Proposal Received by: Dennis L. Hamel  
Plugging operations attended by agent? All[     ], Part[ X ], None[     ]

Completed: Hour: 12:00P.M., Day: 27, Month: April, Year: 95

Actual plugging report: Rigged up with Mercury Wireline perf. gun and shot 1096' - 1097' - 1796' - 1797'. P.O.O.H. with perf. gun. Rigged Mercury down. Rig up Murfin. R.I.H. with 117 joints to 2 3/8" tubing - set tubing at 3589'. Rigged up Halliburton mixed and pumped 77 sxs. 60/40 pozmix -10% gel - 1/4# flocele per. sack added 150# hulls. P.O.H with 40 joints and pumped 77 sxs. same mix. P.O.H. 40 joints and pumped 83 sxs. with 100# hulls. P.O.H. with last 37 joints tubing. Tied onto 5 1/2" casing and pumped 30 sxs. pressured to 200# and held. Hooked up to 8 5/8" - 5 1/2" annulus pumped 75 sxs. with 100# hulls. Shut in at 100# and held. Total 340 sxs. cement and 500# hulls.

Remarks:      
Condition of casing(in hole): GOOD X BAD     Anhy.plug: YES X NO      
Bottom plug(in place): YES    , CALC X, NO     Dakota plug: YES X, NO      
Plugged through TUBING    , CASING X. Elevation:     GL

    did X / did not [     ] observe the plugging.

Dennis L. Hamel  
(agent)

INVOICED

DATE 5-10-95  
INV. NO. 42799