

4-041675

4-28

15-137-00722-00-00  
API number: 15- - 12-20-57

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 S. MARKET, ROOM #2078  
WICHITA, KANSAS 67202

NE NW NE /4 SEC. 36, 05 S, 21 W  
4950 feet from S section line  
1650 feet from E section line

Operator license# 5447 Lease Veeh 'A' well # 14

Operator: OXY USA, Inc. County Norton 119.54

Address: 110 S. Main Well total depth 3678 feet  
Suite #800 Conductor Pipe: 0 inch @ 0 feet  
Wichita, Kansas 67202 Surface pipe 8 5/8 Inch @ 240 feet  
w/200 sxs.

Aband. oil well X, Gas well    , Input well    , SWD    , D & A    

Plugging contractor: Halliburton Cementing License#    

Address: Hays, Kansas 67601

Company to plug at: Hour: 9:00A.M. Day: 28 Month: April Year: 95

Plugging proposal received from: Jim Nowell

Company: OXY USA, Inc. Phone:    

Were: 5 1/2" casing set at 3676' w/200 sxs. cement.  
Anhy. at 1843' - Dakota at 1143'. D.V. at 1835' w/400 sxs.cmt. & 200 cu.ft.  
Ordered 400 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls.

STATE CORPORATION COMMISSION

MAY 04 1995  
05-09-1995  
WICHITA, KANSAS

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All[     ], Part[ X ], None[     ]

Completed: Hour: 12:00P.M., Day: 28, Month: April, Year: 95

Actual plugging report: Rigged up and R.I.H. with Mercury Wireline perf gun.  
Perforated at 1143' - 1144' - 1843' - 1844'. P.O.O.H. with perf. gun and  
rigged wireline down. Rigged up Halliburton - hooked to 5 1/2" casing.  
Started pumping 60/40 pozmix - 10% gel - 1/4# flocele with 5 sxs. cement with  
400# hulls. Hit 2000# pressure with 123 sxs. cement in 5 1/2". Held.  
Hooked-up to 8 5/8" - 5 1/2" annulus - pumped 2 sxs. same mix with 100# hulls  
and hit 675# pressure - held.

Remarks:    

Condition of casing(in hole): GOOD X BAD     Anhy.plug: YES X NO    

Bottom plug(in place): YES    , CALC X, NO     Dakota plug: YES X, NO    

Plugged through TUBING    , CASING X. Elevation:     GL

**INVOICED**  
I did not [     ] observe the plugging.

Dennis L. Hamel  
(agent)

DATE 5-10-95  
INV. NO. 42803

HD