

4-041676

4-28

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 S. MARKET, ROOM #2078  
WICHITA, KANSAS 67202

API number: 15-137-00721-00-00

SW NW NE /4 SEC. 36, 05 S, 21 W  
4290 feet from S section line  
2310 feet from E section line

Operator license# 5447

Lease Veeh 'A' well # 13

Operator: OXY USA, Inc.

County Norton 119.08

Address: 110 S. Main  
Suite #800  
Wichita, Kansas 67202

Well total depth 3664 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 240 feet  
w/200 sxs.

Aband. oil well X, Gas well    , Input well    , SWD    , D & A    

Plugging contractor: Halliburton Cementing License#           

Address: Hays, Kansas 67601

Company to plug at: Hour: 9:00A.M. Day: 28 Month: April Year: 95

Plugging proposal received from: Jim Nowell

Company: OXY USA, Inc. Phone: 05-09-1995

Were: 5 1/2" casing set at 3660' w/200 sxs. cement.  
Anhy. at 1831' - Dakota at 1131'. D.V. at 1825' w/110 bbls. Kempoc.  
Ordered 400 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All[     ], Part[ X ], None[     ]

Completed: Hour: 12:00P.M., Day: 28, Month: April, Year: 95

Actual plugging report: Rigged up and R.I.H. with Mercury Wireline perf gun.  
Perforated at 1131' - 1132' - 1831' - 1832'. P.O.O.H. with perf. gun and rig  
down. Moved Murfin in and ran in 115 joints 2 3/8" tubing to 3589'. Rigged  
up Halliburton and mixed 77 sxs. 60/40 pozmix - 10% gel - 1/4# flocele per.  
sack with 150# hulls. Pulled to 2388' pumped 77 sxs. cement and 150# hulls.  
Pulled tubing to 1188' - pumped 86 sxs. cement circulated to pit. Pulled out  
of the hole and hooked-up to 5 1/2" casing and pumped 25 sxs. cement with 50#  
hulls to 400# and held. Hooked-up to 8 5/8" - 5 1/2" annulus and pumped 75  
sxs. cement with 50# hulls. Pumped to 400# - held at 250#.

Remarks:  
Condition of casing(in hole): GOOD X BAD     Anhy.plug: YES X NO      
Bottom plug(in place): YES    , CALC X, NO     Dakota plug: YES X, NO      
Plugged through TUBING    , CASING X. Elevation:            GL

I did X did not     observe the plugging.

Dennis L. Hamel  
(agent)

**INVOICED**

DATE 5-10-95

NO. 42804