

4-041674 4-27

TO: 15-137-00720-00-00 API number: 15- - 5-29-57

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 S. MARKET, ROOM #2078
WICHITA, KANSAS 67202

SW SW NE /4 SEC. 36, 05 S, 21 W
2970 feet from S section line
2310 feet from E section line

Operator license# 5447 Lease Veeh 'A' well # 12

Operator: OXY USA, Inc. County Norton 118.79

Address: 110 S. Main Well total depth 3655 feet
Suite #800 Conductor Pipe: 0 inch @ 0 feet
Wichita, Kansas 67202 Surface pipe 8 5/8 Inch @ 240 feet
w/250 sxs.

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Halliburton Cementing License#

Address: Hays, Kansas 67601

Company to plug at: Hour: 9:00A.M. Day: 27 Month: April Year: 95

Plugging proposal received from: Jim Nowell

Company: OXY USA, Inc. Phone:

Were: 5 1/2" casing set at 3651' w/200 sxs. cement.

Anhy. at 1820' - Dakota at 1120..

Ordered 400 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 12:00P.M., Day: 27, Month: April, Year: 95

Actual plugging report: Rigged up and R.I.H. with Mercury Wireline perf gun.
Perforated at 1120' - 1121' - 1805' - 1806'. Rigged down wireline. Rigged
up Halliburton to 5 1/2" casing. Started pumping 60/40 pozmix - 10% gel -
1/4# flocele per. sack with 400# hulls. Pumped 255 sxs. cement - shut in at
1200# P.S.I. Held 400#. Hooked-up to 8 5/8" - 5 1/2" annulus and pumped 105
sxs. cement with 100# hulls same cement. Shut in and held 75#.

RECEIVED
STATE CORPORATION COMMISSION

MAY 09 1995
05-09-1995

Remarks:

Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO

Bottom plug(in place): YES , CALC X, NO Dakota plug: YES X, NO

Plugged through TUBING , CASING X. Elevation: GL

INVOICED

I did not[] observe the plugging.

Dennis L. Hamel
(agent)

DATE 5-10-95

INV. NO. 42801