

11-7 4-041845

15-137-00601-00-00
API Number: 15- - 06-03-60

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

NE SW NW /4 SEC. 36, 05 S, 21 W
3630 feet from S section line
4290 feet from E section line

Operator license# 5447

Lease: Kitzke Well # 11

Operator: OXY USA, Inc.

County: Norton 119.60

Address: P.O. Box 300
Tulsa, Oklahoma 74102-0300

Well total depth 3680 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 245 feet
w/200 sxs.cmt.

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Halliburton Cementing, Inc. License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: 8:00 A.M. Day: 7 Month: November Year 1996

Plugging proposal received from: Jim Nowell

Company: OXY USA, Inc. Phone: 918-561-3564

Were: 5 1/2" casing set at 3678' w/200 sxs.
Open hole.

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All[], Part[X], None[]

01-10-1997

Completed: Hour: 9:45 A.M., Day: 7, Month: November, Year: 1996

Actual plugging report: Dug out casing and orange peeled 5 1/2" to 8 5/8" casing. Install 2" riser to surface. Rigged up H.L.S. & perf at 1170' and 1815' with 2 spf. MIRU Murfin Drilling, RIH with 2 3/8" tubing. Open ended to 3620'. Pumped 65 sxs MIDCON 2 with 2% CC and 300# cottonseed hulls. Pulled 48 jts. to 2150'. Pumped 65 sxs cement & 200# hulls. Pulled tubing to 600'. Pumped 35 sxs cement and circulated to surface. POOH with rest of tubing. Hooked up to 5 1/2" casing and pumped 15 sxs cement. Max. P.S.I. 550#. Closed in 5 1/2" at 250# pressure. Hooked up to 8 5/8" casing and pumped 50 sxs MIDCON 2 cement with 2% CC and 100# hulls. Max. P.S.I. 210#. S.I.P. 50#. Total 215 sxs cement used.

Remarks: Allied Cementing.
Condition of casing(in hole): GOOD X BAD
Bottom plug(in place): YES X, CALC, NO
Plugged through TUBING X, CASING
Anhy.plug: YES X NO
Dakota plug: YES X, NO
Elevation: 2246 G.L.

I did [] / did not [] observe the plugging.

Dennis L. Hamel
(agent)

INVOICED
DATE JAN 10 1997
INV. NO. 47320