

11-6 4-041844 15-137-00600-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- - 10-25-57

SW NW NW /4 SEC. 36 , 05 S, 21 W
4290 feet from S section line
4950 feet from E section line

Operator license# 5447
Operator: OXY USA, Inc.
Address: P.O. Box 300
Tulsa, Oklahoma 74102-0300

Lease: Kitzke Well # 8
County: Norton 120.02
Well total depth 3693 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 245 feet
w/200 sxs.cmt.

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Halliburton Cementing, Inc. License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: 1:00 P.M. Day: 6 Month: November Year 1996

Plugging proposal received from: Jim Nowell

Company: OXY USA, Inc. Phone: 918-561-3564

Were: 5 1/2" casing set at 3690' w/200 sxs.
Open hole. D.V. at 1845' w/400 sxs - surface.

01-10-1997

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All [], Part [X], None []

Completed: Hour: 2:30 P.M., Day: 6, Month: November, Year: 1996

Actual plugging report: Dug out casing and orange peeled 5 1/2" to 8 5/8" casing. Install 2" riser to surface. This well has a D.V. tool at 1845'. Cemented with 400 sxs 50/50 pozmix and 200 cu ft strata-crete. MIRU Murfin Drilling, R.I.H. with 2 3/8" tubing. Open ended to 3660'. Pumped 65 sxs MIDCON 2 with 2% C.C. and 300# cottonseed hulls. Pulled 48 jts. to 2100'. Pumped 65 sxs cement and 200# hulls. Pulled tubing to 600'. Pumped 30 sxs cement and circulated to surface. POOH with rest of tubing. Hooked up to 5 1/2" casing and pumped 15 sxs cement. Max. P.S.I. 500#. S.I.P. 500#. Hooked up to 8 5/8" casing and pumped 5 sxs MIDCON 2 cement with 2% C.C. and zero lbs hulls. Max. P.S.I. 500#. S.I.P. 500#. Rig down. Total cement used 180 sxs.

Remarks: Allied Cementing.
Condition of casing(in hole): GOOD X BAD
Bottom plug(in place): YES X, CALC, NO
Plugged through TUBING X, CASING. Elevation: 2257 G.L.
Anhy.plug: YES X NO
Dakota plug: YES X, NO

I did [] observe the plugging.

Dennis L. Hamel (agent)

INVOICED
DATE JAN 10 1997
INV. NO. 47320