

11-7

4-041843

15-137-00599-00-00

API Number: 15- - 07-31-57

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

NE NE NW /4 SEC. 36, 05 S, 21 W  
4950 feet from S section line  
2970 feet from E section line

Operator license# 5447

Lease: Kitzke Well # 7

Operator: OXY USA, Inc.

County: Norton 118.62

Address: P.O. Box 300  
Tulsa, Oklahoma 74102-0300

Well total depth 3650 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 240 feet  
w/200 sxs.cmt.

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Halliburton Cementing, Inc. License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: 8:00 A.M. Day: 7 Month: November Year 1996

Plugging proposal received from: Jim Nowell

Company: OXY USA, Inc. Phone: 918-561-3564

Were: 5 1/2" casing set at 3646' w/200 sxs.  
Open hole. D.V. at 1819' w/400 sxs - surface.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All[ ], Part[ X ], None[ ]

Completed: Hour: 9:15 A.M., Day: 7, Month: November, Year: 1996

Actual plugging report: Dug out casing and orange peeled 5 1/2" to 8 5/8" casing. Install 2" riser to surface. This well has a D.V. tool at 1821'. Cemented with 400 sxs 50/50 pozmix and 200 cu ft strata-crete. MIRU Murfin Drilling, R.I.H. with 2 3/8" tubing. Open ended to 3600'. Pumped 65 sxs MIDCON 2 with 2% C.C. and 300# cottonseed hulls. Pulled 48 jts. to 2100'. Pumped 65 sxs cement and 200# hulls. Pulled tubing to 600'. Pumped 30 sxs cement and circulated to surface. POOH with rest of tubing. Hooked up to 5 1/2" casing and pumped 25 sxs cement. Max. P.S.I. 600#. S.I.P. 600#. Hooked up to 8 5/8" casing and pumped 5 sxs MIDCON 2 cement with 2% C.C. and zero lbs hulls. Max. P.S.I. 400#. Rig down. Total cement used 190 sxs.

Remarks: Allied Cementing.  
Condition of casing(in hole): GOOD X BAD  
Bottom plug(in place): YES X, CALC, NO  
Plugged through TUBING X, CASING. Elevation: 2216 K.B.  
Anhy.plug: YES X NO  
Dakota plug: YES X, NO

I did [ ] did not [ ] observe the plugging.

Dennis L. Hamel (agent)

Form CP-2/3

INVOICED  
DATE JAN 10 1997  
INV. NO. 47321

01-10-1997