

X  
4-041842

15-137-00598-00-00

"CORRECTED"

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15- - 06-23-57

SW NE NW /4 SEC. 36 , 05 S, 21 W  
6290 feet from S section line  
3630 feet from E section line

Operator license# 5447

Lease: Kitzke Well # 6

Operator: OXY USA, Inc.

County: Norton

Address: P.O. Box 300  
Tulsa, Oklahoma 74102-0300

Well total depth 3664 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 240 feet  
w/200 sxs.cmt.

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Halliburton Cementing, Inc. License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: 1:00 P.M. Day: 7 Month: November Year 1996

Plugging proposal received from: Jim Nowell

Company: OXY USA, Inc. Phone: 918-561-3564

Were: 5 1/2" casing set at 3648' w/400 sxs.  
D.V. at 1837' w/400 sxs - surface.

RECEIVED  
KANSAS CORP. DIV.  
02-25-1997  
11:23 AM

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All [ ], Part [ X ], None [ ]

Completed: Hour: 2:30 P.M., Day: 7, Month: November, Year: 1996

Actual plugging report: Dug out casing and orange peeled 5 1/2" to 8 5/8" casing. Install 2" riser to surface. This well has a D.V. tool at 1837'. Cemented with 400 sxs 50/50 pozmix and 200 cu ft strata-crete. MIRU Murfin Drilling, R.I.H. with 2 3/8" tubing. Open ended to 3620'. Pumped 65 sxs MIDCON 2 with 2% C.C. and 200# cottonseed hulls. Pulled 48 jts. to 2150'. Pumped 65 sxs cement and 200# hulls. Pulled tubing to 600'. Pumped 25 sxs cement and circulated to surface. POOH with rest of tubing. Hooked up to 5 1/2" casing and pumped 20 sxs cement. Max. P.S.I. 500#. S.I.P. 275#. Hooked up to 8 5/8" casing and pumped 2 sxs MIDCON 2 cement with 2% C.C. and zero lbs hulls. Rig down. Total cement used 175 sxs.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD X BAD

Anhy.plug: YES X NO

Bottom plug(in place): YES X, CALC, NO

Dakota plug: YES X, NO

Plugged through TUBING X, CASING. Elevation: 2220 G.L.

I did [ X ] / did not [ ] observe the plugging.

Dennis L. Hamel  
(agent)

11-7

4-041842 15-137-00598-00-00

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15- - 06-23-57

SW NE NW /4 SEC. 36, 05 S, 21 W  
3630 feet from S section line  
4290 feet from E section line

Operator license# 5447

Lease: Kitzke Well # 6

Operator: OXY USA, Inc.

County: Norton 119.08

Address: P.O. Box 300  
Tulsa, Oklahoma 74102-0300

Well total depth 3664 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 240 feet  
w/200 sxs.cmt.

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Halliburton Cementing, Inc. License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: 1:00 P.M. Day: 7 Month: November Year 1996

Plugging proposal received from: Jim Nowell

Company: OXY USA, Inc. Phone: 918-561-3564

Were: 5 1/2" casing set at 3648' w/400 sxs.  
D.V. at 1837' w/400 sxs - surface.

11-10-10

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All [ ], Part [ X ], None [ ]

Completed: Hour: 2:30 P.M., Day: 7, Month: November, Year: 1996

Actual plugging report: Dug out casing and orange peeled 5 1/2" to 8 5/8" casing. Install 2" riser to surface. This well has a D.V. tool at 1837'. Cemented with 400 sxs 50/50 pozmix and 200 cu ft strata-crete. MIRU Murfin Drilling, R.I.H. with 2 3/8" tubing. Open ended to 3620'. Pumped 65 sxs MIDCON 2 with 2% C.C. and 200# cottonseed hulls. Pulled 48 jts. to 2150'. Pumped 65 sxs cement and 200# hulls. Pulled tubing to 600'. Pumped 25 sxs cement and circulated to surface. POOH with rest of tubing. Hooked up to 5 1/2" casing and pumped 20 sxs cement. Max. P.S.I. 500#. S.I.P. 275#. Hooked up to 8 5/8" casing and pumped 2 sxs MIDCON 2 cement with 2% C.C. and zero lbs hulls. Rig down. Total cement used 175 sxs.

Remarks: Allied Cementing.  
Condition of casing(in hole): GOOD X BAD  
Bottom plug(in place): YES X, CALC, NO  
Plugged through TUBING X, CASING. Elevation: 2220 G.L.  
Anhy.plug: YES X NO  
Dakota plug: YES X, NO

I did [ X ] / did not [ ] observe the plugging.

Dennis L. Hamel (agent)

INVOICED  
DATE JAN 10 1997  
INV. NO. 47322