

4-041672 4-27 15-137-00761-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 S. MARKET, ROOM #2078
WICHITA, KANSAS 67202

API number: 15- - 7-13-46
NE NE NE /4 SEC. 36, 05 S, 21 W
4950 feet from S section line
330 feet from E section line

Operator license# 5447 Lease Veeh 'A' well # 6

Operator: OXY USA, Inc. County Norton 118.20

Address: 110 S. Main Well total depth 3637 feet
Suite #800 Conductor Pipe: 0 inch @ 0 feet
Wichita, Kansas 67202 Surface pipe 8 5/8 Inch @ 208 feet
w/175 sxs.

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Halliburton Cementing License#

Address: Hays, Kansas 67601

Company to plug at: Hour: 9:00A.M. Day: 27 Month: April Year: 95

Plugging proposal received from: Jim Nowell

Company: OXY USA, Inc. Phone:

Were: 5 1/2" casing set at 3635' w/150 sxs. cement.
Anhy. at 1805' - Dakota at 1105'.
Ordered 400 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls.

STATE CORPORATION COMMISSION

MAY 04 1995
05-09-1995

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 12:00P.M., Day: 27, Month: April, Year: 95

Actual plugging report: Rigged up with Mercury Wireline perf. gun - shot
1105' - 1106' - 1805' - 1806'. P.O.O.H. with perf. gun. Rigged Mercury
down. Rig up Halliburton. Mixed and pumped 50 sxs. 60/40 pozmix - 10% gel -
1/4# flocele per. sack - 400# hulls. Topped 5 1/2" casing started leaking.
Shut down - called welder. Started pumping cement down 5 1/2" same mix.
Pressured to 600# with 255 sxs. down and held at 400#. Hooked up to 8 5/8" -
5 1/2" annulus and pumped 75 sxs. at 600# pressure with no hulls. Held at
400#. Total of 330 sxs. cement - 400# hulls.

Remarks:
Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO
Bottom plug(in place): YES , CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: GL

INVOICED

did not [] observe the plugging.

Dennis L. Hamel
(agent)

DATE 5-10-95
INV. NO. 42800