

15-147-00915-000

4-041670 4-26

KCC cfb

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 S. MARKET, ROOM #2078  
WICHITA, KANSAS 67202

API number: 15- - 8-21-49  
NE NE NW /4 SEC. 31, 05 S, 21 W  
330 feet from N section line  
2310 feet from W section line

Operator license# 5447

Lease Veeh 'A' well # 7

Operator: OXY USA, Inc.

County Phillips Norton <sup>KCC</sup> <sub>CFB</sub> 118.04

Address: 110 S. Main  
Suite #800  
Wichita, Kansas 67202

Well total depth 3632 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 175 feet  
w/200 sxs.

Aband. oil well X, Gas well    , Input well    , SWD    , D & A    

Plugging contractor: Halliburton Cementing License#    

Address: Hays, Kansas 67601

Company to plug at: Hour: 9:00A.M. Day: 26 Month: April Year: 95

Plugging proposal received from: Jim Nowell

Company: OXY USA, Inc. Phone:    

Were: 5 1/2" casing set at 3632' w/150 sxs. cement.  
Perfs. at 3608' - 3618'. Anhy. at 1792' - Dakota at 1092'.  
Ordered 400 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls.

RECEIVED  
STATE CORPORATION COMMISSION

Plugging Proposal Received by: Dennis L. Hamel  
Plugging operations attended by agent? All [ Part ] None [     ]

MAY 04 1995  
05-04-1995  
WICHITA, KANSAS

Completed: Hour: 12:00P.M., Day: 26, Month: April, Year: 95

Actual plugging report: R.I.H. with Mercury Wireline and perf. gun and shot  
1092' - 1093' - 1792' - 1793'. P.O.O.H. with perf. gun and rigged down.  
Rigged up Murfin - R.I.H. with 114 joints 2 3/8" tubing to 3493'. Mixed 77  
sxs. 60/40 pozmix - 10% gel - 1/4# sx. flocele - 200# hulls. Pumped to  
bottom. Pulled to 2293' and pumped 77 sxs. same mix and hulls. Pulled to  
1150' and hooked-up and circulated good cement to pit. P.O.O.H. with rest  
of tubing. Put on swedge. Topped off casing at 300#. Hooked-up to 8 5/8" -  
5 1/2" annulus and pumped 136 sxs. - 100# hulls at 400# shut in and held at  
100#.

Remarks:      
Condition of casing(in hole): GOOD X BAD     Anhy.plug: YES X NO      
Bottom plug(in place): YES    , CALC X, NO     Dakota plug: YES X, NO      
Plugged through TUBING    , CASING X. Elevation:     GL

I did [X] / did not [     ] observe the plugging.

Dennis L. Hamel  
(agent)

**INVOICED**  
DATE 5-10-95  
INV. NO. 428024