

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-00540-00-00

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
FEB 5 1963
2-5-63
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Continental Oil Co

Complete Address: Drawer # 367, Plainville, Kansas.

Lease Name Feely Well No. 3

Location SE-NE-SW Sec. 2 Twp. 5 Rge. (E) (W) 27

County Decatur Total Depth 3820

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Co

Address: Chase, Kansas License No. 436

Operation Completed: Hour 1:30P Day 2 Month 2 Year 1963

The Above well was plugged as follows:

268' 9 5/8" Surface casing cement circulated. 5 1/2" Set @ 3819'.

Well plugged back to 3670', Top perforation @ 3619'. Sanded well back to 3600', dumped 4 sx. cement with dump bailer. Pulled 1200' 5 1/2".

Set bridge & plug @ 550' with 20 Sx cement. Mud to 315', set plug & 20 Sx to 258'. Well Left as water well for Continental Oil Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols
Well Plugging Supervisor

DATE 2-8-63

INV. NO. 6550-W