

KANSAS

Form CP-3  
Rev. 6-4-68

## STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-039-20218-00-00

RECEIVED  
STATE CORPORATION COMMISSION

OCT 19 1971

CONSERVATION DIVISION  
Wichita, Kansas

10-19-71

Operator's Full Name Murfin Drilling Company,Complete Address 617 Union Center, Wichita, Kansas.Lease Name Tacha Well No. 1Location SW-SW-NE Sec. 1 Twp. 5 Rge. (E) (W) 27County Decatur Total Depth 3745'Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XOther well as hereafter indicated       Plugging Contractor AboveAddress        License No.       Operation Completed: Hour 1:30 PM Day 15 Month 10 Year 1971

The above well was plugged as follows:

230'--8 5/8" Surface casing, cement circulated with 175 Sx.  
Top of Dakota Section @ 1000'.Circulated hole with heavy mud. Pulled DP to 1225' and displaced 100 Sx. cement thru  
DP from 1225' to 900'. Pulled DP to 245' and displaced 25 Sx. cement thru DP from  
245' to 170'. Pulled DP, set bridge @ 40' with  $\frac{1}{2}$  sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: R. L. Dachal  
Well Plugging SupervisorDATE 10-19-71INV. NO. 4496-10