

KANSAS

JP
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-20017-00-00

RECEIVED
STATE CORPORATION COMMISSION

JUL 25 1967

725-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Raymond Oil Company, Incorporated,

Complete Address: 410 4th National Bank Building, Wichita, Kansas.

Lease Name Feely Well No. 1

Location NE-SW-NW Sec. 2 Twp. 5 Rge. (E) (W) 27

County Decatur Total Depth 3828'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Murfin Drilling Company,

Address: 617 Union Center, Wichita, Kansas. License No.

Operation Completed: Hour 1:30PM Day 18 Month 7 Year 1967

The Above well was plugged as follows:

273'--8 5/8" Surface pipe, cement circulated with 150 Sx.
Dakota section from 1100' to 1250'.

Circulated hole with heavy mud, set plug @ 1290' and displaced 75 Sx.
cement thru DP. to 1000'. Pulled DP to 275' and displaced 20 Sx. cement
thru DP. 215'. Pulled DP. Set plug with 1/2 sack hulls and 10 Sx. cement
to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *M. L. Dehals*
Well Plugging Supervisor

INVOICED

DATE 7/26/67

INV. NO. 6026-4