

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-00573-00-00

RECEIVED

STATE CORPORATION COMMISSION

SEP 4 1968

CONSERVATION DIVISION
Wichita, Kansas

9-4-68

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Continental Oil Company,

Complete Address: Box #267, Great Bend, Kansas.

Lease Name C. E. Feely Well No. 2

Location NW-SE-SW Sec. 2 Twp. 5 Rge. (E) (W) 27

County Decatur Total Depth 3710'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Russ Casing Pulling, Incorporated,

Address: Box #1082, Great Bend, Kansas. License No. 623

Operation Completed: Hour 10:30 AM Day T Month 9 Year 1968

The Above well was plugged as follows:

248'--10 3/4" Surface casing, cement circulated. (9" Hole).

3709'--7" OD Production casing cemented back to 3000'.

Sanded well back to 3370' and set 5 Sx. cement with dump bailer. Pulled 7" casing and
squeezed well with 9 sacks hulls using 5 sacks hulls in initial gel and followed with
130 Sx. cement from 1350' to 1025', then 25 sacks gel from 1025' to 275' and followed
with 30 Sx. cement from 275' to 200'. Then 6 sacks gel from 200' to 30' and finally
15 Sx. cement to bottom of cellar. Maximum pump-in pressure-400#. Final shut-in
pressure-200#. (Mudding and cementing operations by Halliburton).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: A. L. Nichols
Well Plugging Supervisor

DATE 9/4/68
INV. NO. 8408-u