

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-00542-00-00

12-23-71  
RECEIVED  
STATE CORPORATION COMMISSION  
DEC 23 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Continental Oil Company,  
Complete Address 3535 NW 58th Street, Oklahoma City, Oklahoma.  
Lease Name Feely LKC Unit Well No. 1  
Location SE-NW-SW Sec. 2 Twp. 5 Rge. (E) (W) 27  
County Decatur Total Depth 3700'  
Abandoned Oil Well X Gas Well        Input Well        SWD Well        D & A         
Other well as hereafter indicated         
Plugging Contractor Pipe Pullers, Incorporated,  
Address Box #186, Ellinwood, Kansas. License No. 462  
Operation Completed: 9:00 PM Day 17 Month 12 Year 1971

The above well was plugged as follows:

207'--8 5/8" Surface casing, cement circulated with 175 Sx.  
3699'--5 1/2" Production casing cemented on bottom with 125 Sx. Well plugged back to  
3666'. Top of perforations @ 3607'.  
Sanded well back to 3550' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing  
(1089') and squeezed well initially with 5 sacks gulls and 13 sacks gel and followed  
with 110 Cu. Ft. cement from 1325' to 1000' then 18 sacks gel from 1000' to 275' and  
followed with 30 Cu. Ft. cement from 275' to 200' then 4 sacks gel from 200' to 30'  
and finally 10 Sx. cement from 30' to bottom of cellar. Maximum pump-in pressure--  
250#. Final shut-in pressure--100#. (Mudding and cementing operations by Sun Cementing).

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols  
Well Plugging Supervisor

INVOICED

DATE 1-11-72

INV. NO. 4925-10