

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-00541-00-00

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

12-23-71
RECEIVED
STATE CORPORATION COMMISSION
DEC 23 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Continental Oil Company,
Complete Address 3535 NW 58th Street, Oklahoma City, Oklahoma.
Lease Name Feely LKC Unit Well No. 4
Location SE-SW-SW Sec. 2 Twp. 5 Rge. (E) (W) 27
County Decatur Total Depth 3717'
Abandoned Oil Well Gas Well Input Well SWD Well D & A
Other well as hereafter indicated _____
Plugging Contractor Pipe Pullers, Incorporated,
Address Box #486, Ellinwood, Kansas. License No. 462
Operation Completed: Hour 3:00 PM Day 20 Month 12 Year 1971

The above well was plugged as follows:

200'--8 5/8" Surface casing, cement circulated with 150 Sx.
3716'--5 1/2" Production casing cemented on bottom with 150 Sx. Well plugged back to 3616'. Top of perforations @ 3602'.
Sanded well back to 3550' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing (1047') and squeezed well initially with 5 sacks hulls and 13 sacks gel, gained circulation around surface casing. Ran 2" tubing to 1150' and circulated heavy gel mud with 20 Sx. and spotted 110 Cu. Ft. cement from 1150' to 825', pulled tubing to 250' and spotted 30 Cu. Ft. cement from 250' to 175'. Pulled tubing and filled hole to bottom of cellar with 10 Cu. Ft. cement. (Mudding and cementing by Sun Cementing).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. J. Dickels
Well Plugging Supervisor

DATE 1-11-72

INV. NO. 4926-10