

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
OCT 24 1966
10-24-1966
CONSERVATION DIVISION
WICHITA, KANSAS

15-137-30110-00-00

Operator's Full Name Abercrombie Drilling, Incorporated.

Complete Address: 801 Union Center, Wichita, Kansas.

Lease Name Otter Well No. 1

Location CNE-NE Sec. 21 Twp. 5 Rge. (E) (W)25

County Norton Total Depth 4040

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 9:00AM Day 21 Month 10 Year 1966

The Above well was plugged as follows:

255' -- 7" OD Surface pipe, cement circulated (6 1/2" hole)
Circulated hole with heavy mud, set plug @ 600' and displaced 15 Sx.
cement thru DP. Heavy mud to 240', set plug with 1/2 sack hulls and dis-
placed 15 Sx. cement thru DP. Heavy mud to 40', set plug with 1/2 sack
hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols
Well Plugging Supervisor

DATE 10/24/66
INV. NO. 4163-4