

KANSAS

JL
STATE CORPORATION COMMISSION
RECEIVED
11-16-1970
NOV 16 1970
CONSERVATION DIVISION
Wichita, Kansas

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-127-20023-00-00

Operator's Full Name National Associated Petroleum,

Complete Address Petroleum Building, Tulsa, Oklahoma.

Lease Name Agnes Mindrup Well No. 1

Location CNW-SW Sec. 14 Twp. 5 Rge. (E) (W) 25

County Norton Total Depth 4010'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor L. J. Dreiling and Sons, Incorporated,

Address R. R. #2, Victoria, Kansas. License No.

Operation Completed: Hour 10:00 PM Day 10 Month 11 Year 1970

The above well was plugged as follows:

250'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 1025'.

Circulated hole with heavy mud. Pulled DP to 1250' and displaced 100 Sx. cement thru
DP from 1250' to 925'. Pulled DP to 260' and displaced 25 S x. cement thru DP from
260' to 185'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *W. D. Nichols*
Well Plugging Supervisor

INVOICED

DATE 11-16-70

INV. NO. 2865-W