

*Y*  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

15-137-00153-00-00

RECEIVED  
STATE CORPORATION COMMISSION

MAR 16 1966  
03-16-1966  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Francis Weigel,  
Complete Address: Gorham, Kansas.  
Lease Name Spieess Well No. 1  
Location NW-NW-SW Sec. 35 Twp. 5 Rge. (E) (W) 25  
County Norton Total Depth 4055  
Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A       
Other well as hereafter indicated:       
Plugging Contractor: Glenn & Smith Pipe Pulling Company,  
Address: 204 E. 6th, Ellinwood, Kansas. License No. 396  
Operation Completed: Hour 9:00AM Day 14 Month 3 Year 1966

The Above well was plugged as follows:

245'--8 5/8" Surface pipe, cement circulated with 150 Sx.  
3727'--4 1/2" Production casing cemented with 120 Sx. Open hole completion.

Pushed plug to 3700' and set 5 Sx. cement with dump bailer.

Pull 4 1/2" casing. Ran bailer and found top of fluid @ 300'. Set wood  
and rock bridge @ 300' and filled hole to bottom of cellar using 5 yards  
Redi-Mix cement.

I hereby certify that the above well was plugged as herein stated.

Signed: *A. L. Nichols*  
Well Plugging Supervisor

INVOICED

DATE 3/16/66  
INV. NO. 2882-W