

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-137-20056-00-00

Operator's Full Name Leben et al,

Complete Address 200 West Douglas, Wichita, Kansas.

Lease Name Noone Well No. 1

Location 150' SW of <sup>SW</sup> CSE-SE Sec. 34 Twp. 5 Rge. (E) (W) 25

County Norton Total Depth 3790'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Leben Drilling, Incorporated,

Address Box #186, Great Bend, Kansas. License No.       

Operation Completed: Hour 8:30 PM Day 17 Month 5 Year 1970

The above well was plugged as follows:

219'--8 5/8" Surface casing, cement circulated.  
Top of Dakota section @ 1025'.

Circulated hole with heavy mud. Pulled DP to 1250' and displaced 100 Sx. cement thru  
DP from 1250' to 925'. Pulled DP to 245' and displaced 25 Sx. cement thru DP from  
245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 20 1970  
CONSERVATION DIVISION  
Wichita, Kansas

Signed: W. L. Nichols  
Well Plugging Supervisor

INVOICED

DATE 5/22/70  
INV. NO. 1923-W