

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-20023-00-00

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

SEP 6 1967
9-6-67
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Abercrombie Drilling Inc.

Complete Address: 801 Union Center Wichita, Kansas

Lease Name Boland Well No. 1

Location 100' S NE NW NE Sec. 15 Twp. 5 Rge. 27 (E) (W) X

County Decatur Total Depth 3824

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Co. Tools

Address: License No.

Operation Completed: Hour 4:30 A Day 2 Month 9 Year 1967

The Above well was plugged as follows:

RTD 3824' 7" csg set at 252' cwc 150 sc.

Gunned pits, circulated heavy mud, set cementing plug at 1500' and displaced 65 sc cem. thru drill pipe. Heavy mud to 240' set cementing plug and displaced 10 sc cement thru drill pipe. Heavy mud to 40' set cementing plug, 1/4 sc hulls and 5 sc cement to base of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9/7/67

INV. NO. 6290-W

Signed: Geo F. Messer
Well Plugging Supervisor