

KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-20033-06-00

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
JAN 2 1969
CONSERVATION DIVISION
Wichita, Kansas
1-2-69

Operator's Full Name E. K. Edmiston,

Complete Address: 425 First National Bank Building, Wichita, Kansas.

Lease Name Feely Well No. 1

Location NE-SW-SE Sec. 22 Twp. 5 Rge. (E) (W) 27

County Decatur Total Depth 3930'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Southwest Casing Pulling Company, Incorporated,

Address: Box #364, Great Bend, Kansas. License No. 9

Operation Completed: Hour 3:30 PM Day 28 Month 12 Year 1968

The Above well was plugged as follows:

242'--8 5/8" Surface casing, cement circulated with 125 Sx.
3929'--4 1/2" Production casing cemented on bottom with 125 Sx. Top of cement @ 3440'.
Top perforations from 3709 to 3713'.

Sanded well back to 3650' and set 4 Sx. cement with dump bailer. Pulled 4 1/2" casing
and squeezed well with initially with 5 sacks hulls and 9 sacks gel and followed with
100 Sx. cement from 1450' to 1125', then 21 sacks gel from 1125' to 275' and followed
with 20 Sx. cement from 275' to 215' then 5 sacks gel from 215' to 30' and finally 10
Sx. cement from 30' to bottom of cellar. Maximum pump-in pressure--200#. Final shut-
in pressure--100#. (Mudding and cementing operations performed by Sun Cementing Co.)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Dicks
Well Plugging Supervisor

DATE 1-2-69
INV. NO. 9131-W