

40
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT
15-039-00576-00-00

RECEIVED
STATE CORPORATION COMMISSION

AUG 31 1964
8-31-64
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Continental Oil Company,

Complete Address: Box #267, Great Bend, Kansas.

Lease Name C. E. Feely Well No. 1

Location *C NWSE NE*
1650' FNL and 990' FEL Sec. 22 Twp. 5 Rge. (E) (W) 27

County Decatur Total Depth 3898

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling Company, Incorporated,

Address: Box #221, Great Bend, Kansas License No. 49

Operation Completed: Hour 1:30PM Day 25 Month 8 Year 1964

The Above well was plugged as follows:

255' -- 8 5/8" Surface pipe, cement circulated with 200 Sx.
3833' -- 5 1/2" cemented with 250 Sx. Well plugged back to 3690'. Top perforations @ 3666'.

Sanded back to 3650' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" to 600' and
circulated heavy gel mud. Pulled 5 1/2" to 540' and displaced 20 Sx. cement thru 5 1/2".
Pulled 5 1/2" to 240' and displaced 20 Sx. cement thru 5 1/2". Pulled 5 1/2", set bridge @
35' and 10 Sx. cement to bottom of cellar.

(Cementing and mudding operations performed by Halliburton Oil Well Cementing Co.)

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 8/31/64
INV. NO. 9935-W

Signed: *H. L. Nichols*
Well Plugging Supervisor