

44  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-00506-00-00

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

SEP 30 1964  
9-30-64  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name R. W. Shields,

Complete Address: 666 4th National Bank Building, Wichita, Kansas.

Lease Name C. E. Feely Well No. 1

Location SE-SE-NE Sec. 22 Twp. 5 Rge. (E) (W) 27

County Decatur Total Depth 3860

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated: (This well was drilled several years ago but never produced.)

Plugging Contractor: Barnes & Sons Pipe Pulling Company,

Address: 1450 Maple, Russell, Kansas License No. 9

Operation Completed: Hour 12:00M Day 26 Month 9 Year 1964

The Above well was plugged as follows:

175'--8 5/8" Surface pipe, cement circulated.  
3859'--5 1/2" Production casing cemented with 175 Sx. Well plugged back to 3627'. Top perforations from 3620' to 3616'.

Sanded well back to 3600' and set 5 Sx. cement with dump bailer.  
Circulated heavy gel mud @ 565' (used 21 Sx. gel). Pulled 5 1/2" to 525' and displaced 20 Sx. cement thru 5 1/2". Pulled 5 1/2" to 200' and displaced 20 Sx. cement thru 5 1/2". Pulled 5 1/2", set bridge @ 35' and 10 Sx. cement to bottom of cellar. (Recovered 745' 5 1/2" casing)

( Mudding and cementing operations performed by Globe Cementing Company)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Scholtz  
Well Plugging Supervisor

DATE 9/30/64  
INV. NO. 9901-w