

DISTRICT CONSERVATION AGENT'S REPORT

15-039-00403-00-00

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. 91-32

LOCATION SE NW NE

SEC. 22 TWP. 5 RGE. 27 W

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 2 Lease Hardesty

Operator Continental Oil Co Address Plainville, Kans

Field \_\_\_\_\_ County Decatur

Total Depth 3729 Feet.

Plugging Contractor West Supply Co

Plugging Contractor's License No. \_\_\_\_\_

Address \_\_\_\_\_

(Describe Briefly the manner in which the well was plugged)

10 3/4" at 200' circulated with cement - 5 1/2" at 3729' with

200 sax cement behind. P.B. to 3690', perforated at 3650',

Filled with sand to 3640', set 4 sax cement with dump bailer,

pulled 1500' 5 1/2" - filled with mud to 240', set rock bridge and 25

sax cement, mud to 30', set rock bridge and 10 sax cement to

bottom cellar.

District Conservation Agent

Date 10-5-56

RECEIVED  
STATE OF KANSAS

6011

10-9-56

PLUGGING  
FILE SEC 22 TWP. 5 RGE. 27 W  
BOOK PAGE 91 LINE 32