

KANSAS

Form CP-3
Rev. 6-9-67

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-20040-00-00

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
APR 29 1968
CONSERVATION DIVISION
Wichita, Kansas
4-29-68

Operator's Full Name Rosen Oil Company, Incorporated,

Complete Address 605 Sutton Place, Wichita, Kansas.

Lease Name Boland Well No. 1

Location NE-SE-NE Sec. 15 Twp. 5 Rge. (E) (W) 27

County Decatur Total Depth 3273

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated _____

Plugging Contractor Abercrombie Drilling, Incorporated,

Address 801 Union Center, Wichita, Kansas. License No. _____

Operation Completed: Hour 2:30 AM Day 21 Month 4 Year 1968

The above well was plugged as follows:

226'--8 5/8" Surface pipe, cement circulated with 175 Sx. (6 3/4" Hole).
Top of Dakota section @ 1325'.

Circulated hole with heavy mud. Pulled DP to 1125' and displaced 80 Sx. cement thru
DP from 1125' to 1100'. Pulled DP to 240' and displaced 15 Sx. cement thru DP from
240' to 180'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: H. D. Nichols
Well Plugging Supervisor

DATE 4/29/68

INV. NO. 4651-W