

15-039-20096-00-00

Form CP-3
Rev. 6-4-68

KANSAS

Y STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
07-14-1969
JUL 14 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Theo. Gore and Leben Drilling, Inc.

Complete Address 650 Fourth National Bank Building, Wichita, Kansas.

Lease Name Coulter Well No. 1

Location SW SW SW
110' ESL & 110' FEL-SW/1 Sec. 30 Twp. 5 Rge. (E) (W) 28

County Decatur Total Depth 4180'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Leben Drilling, Incorporated,

Address Box #186, Great Bend, Kansas. License No.

Operation Completed: Hour 1:30 PM Day 4 Month 7 Year 1969

The above well was plugged as follows:

311'--8 5/8" Surface casing, cement circulated with 250 Sx.
Top of Dakota section @ 1490'.

Circulated hole with heavy mud. Pulled DP to 1725' and displaced 100 Sx. cement thru
DP from 1725' to 1400'. Pulled DP to 335' and displaced 20 Sx. cement thru DP from
335' to 275'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *N. G. Nichols*
Well Plugging Supervisor

DATE 7/14/69
INV. NO. 89-W