

4

KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-039-20101-00-00

Operator's Full Name Petroleum Management, Incorporated,

Complete Address: 1515 Wichita Plaza Building, Wichita, Kansas.

Lease Name Minnick Well No. 1

Location SW SW SE
2200' FEL & 140' FSL of Sec. 20 Twp. 5 Rge. (E) (W) 28

County Decatur Total Depth 4160'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Red Tiger Drilling Company,

Address: 1720 Wichita Plaza Building, Wichita, Kansas. License No.

Operation Completed: Hour 2:15 AM Day 20 Month 7 Year 1969

The Above well was plugged as follows:

290'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 1500'.

Circulated hole with heavy mud. Pulled DP to 1725' and displaced 100 Sx. cement thru
DP from 1725' to 1400'. Pulled DP to 310' and displaced 20 Sx. cement thru DP from 310'
to 250'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of
cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

RECEIVED
STATE CORPORATION COMMISSION
JUL 23 1969

Signed: M. L. Dichel
Well Plugging Supervisor

DATE 7/23/69 CONSERVATION DIVISION
Wichita, Kansas

INV. NO. 139-4