

KANSAS

*pl*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 23 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-039-00048-00-01

Operator's Full Name Continental Oil Company,  
Complete Address 3535 NW 58th Street, Oklahoma City, Oklahoma.  
Lease Name Feely LKC Unit Well No. 5  
Location SE-SE-SW Sec. 2 Twp. 5 Rge. (E) (W) 27  
County Decatur Total Depth 4040'  
Abandoned Oil Well          Gas Well          Input Well X SWD Well          D & A           
Other well as hereafter indicated           
Plugging Contractor Pipe Pullers, Incorporated,  
Address Box #486, Ellinwood, Kansas. License No. 462  
Operation Completed: Hour 11:00 AM Day 17 Month 12 Year 1971

The above well was plugged as follows:

249'--10 3/4" Surface casing, cement circulated with 200 Sx.  
3730' 5 1/2" Production casing cemented on bottom with 200 Sx. Well plugged back to 3640'.  
Top of perforations @ 3590'.

Sanded well back to 3550' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing  
(1215') and squeezed well initially with 5 sacks hulls and 20 sacks gel and followed  
with 150 Cu. Ft. cement from 1325' to 1000' then 22 sacks gel from 1000' to 275' and  
followed with 35 Cu. Ft. cement from 275' to 200' then 7 sacks gel from 200' to 25'  
and finally 10 Cu. Ft. cement from 25' to bottom of cellar. Maximum pump-in pressure  
-350#. Final shut-in pressure-175#. (Mudding and cementing operations by Sun Cementing).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *N. L. Pichels*  
Well Plugging Supervisor

DATE 1-11-72

INV. NO. 4927-112