

KANSAS

4
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-00543-00-~~88~~
01

RECEIVED
STATE CORPORATION COMMISSION
DEC 23 1971
CONSERVATION DIVISION
Wichita, Kansas
12-23-71

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Continental Oil Company,

Complete Address 3535 NW 58th Street, Oklahoma City, Oklahoma, K

Lease Name Feely LKC Unit Well No. 8

Location SE-NE-NW Sec. 11 Twp. 5 Rge. (E) (W) 27

County Decatur Total Depth 3630'

Abandoned Oil Well Gas Well Input Well X SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Pipe Pullers, Incorporated,

Address Box # 486, Ellinwood, Kansas. License No. 462

Operation Completed: Hour 10:30 AM Day 22 Month 12 Year 1971

The above well was plugged as follows:

247'--8 5/8" Surface casing, cement circulated with 175 Sx.
3648'--5 1/2" casing cemented on bottom with 200 Sx. Well plugged back to 3624' Top of perforations @ 3576'.

Sanded well back to 3550' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing and squeezed well initially with 5 sacks hulls and 13 sacks gel then 110 Cu. Ft. cement from 1325' to 1000' then 18 sacks gel from 1000' to 275' and followed with 30 Cu. Ft. cement from 275' to 200' then 4 sacks gel from 200' to 30' and finally 10 Cu. Ft. cement from 30' to bottom of cellar. Maximum pump-in pressure-200#. Final shut-in pressure--100#. (Mudding and Cementing by Sun Cementing).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *W. L. Pichel*
Well Plugging Supervisor

DATE 1-11-72
INV. NO. 4930-W