

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-00574-00-~~01~~
01

RECEIVED
STATE CORPORATION COMMISSION
DEC 23 1971
CONSERVATION DIVISION
Wichita, Kansas
12-23-71

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Continental Oil Company,
Complete Address 3535 NW 58th Street, Oklahoma City, Oklahoma.
Lease Name Feely LKC Unit Well No. 7
Location NW-NE-NW Sec. 11 Twp. 5 Rge. (E) (W) 27
County Decatur Total Depth 3691'
Abandoned Oil Well Gas Well Input Well X SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Pipe Pullers, Incorporated,
Address Box #486, Ellinwood, Kansas. License No. 462
Operation Completed: Hour 5:00 PM Day 20 Month 12 Year 1971

The above well was plugged as follows:

230'--10 3/4" Surface casing, cement circulated with 200 Sx.
370'--7" OD Production casing cemented on bottom with 200 Sx. Well plugged back to
3674'. Top of perforations @ 3590'.

Squeezed well initially with 5 sacks hulls and 20 sacks gel and followed with 150 Cu. Ft.
cement from 1325' to 1000' then 22 sacks gel from 1000' to 275' and followed with 35
Cu. Ft. cement from 275' to 200' then 7 sacks gel from 200' to 25' and finally 10 Cu.
Ft. cement from 25' to bottom of cellar. Maximum pump-in pressure-200#. Final shut-
in pressure-100#. (Mudding and cementing operations by Sun Cementing).

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 1-11-72

INV. NO. 429 4929-W

15-039-00574-00-01

Evidently TD of 3691' shown on
Plugging Authority is a "Drilled out Td",
7" casing is shown set @ 3707'

Bill -