

KANSAS

Form CP-3
Rev. 6-4-68

J
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-~~1455~~00-~~80~~
00575 01

RECEIVED
STATE CORPORATION COMMISSION
DEC 23 1971
CONSERVATION DIVISION
Wichita, Kansas

12-23-71

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Continental Oil Company,
Complete Address 3535 NW 58th Street, Oklahoma City, Oklahoma.
Lease Name Feely LKC Unit Well No. 6
Location NW-NW-NE Sec. 11 Twp. 5 Rge. (E) (W) 27
County Decatur Total Depth 3840'
Abandoned Oil Well Gas Well Input Well X SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Pipe Pullers, Incorporated,
Address Box #486, Ellinwood, Kansas. License No. 462
Operation Completed: Hour 12:45 PM Day 22 Month 12 Year 1971

The above well was plugged as follows:

209'--8 5/8" Surface casing, cement circulated with 150 Sx.
3679'--5 1/2" casing cemented on bottom with 125 Sx. Well plugged back to 3679'. Top of perforations @ 3650'.

Sanded well back to 3625' and set 5 Sx. cement with dump bailer. Attempted to pull 5 1/2" casing and found surface casing loose. Pulled 5 1/2" casing (918') and ran 2" tubing to top of shot joint @ 918', circulated heavy jel mud thru tubing @ 918' then displaced 110 Cu. Ft. cement thru tubing from 918' to 600'. Pulled tubing to 250' and and displaced 30 Cu. Ft. cement from 250' to 30'. Pulled tubing and filled hole from 30' to bottom of cellar with 10 Cu. Ft. cement. (Mudding and cementing by Sun Cemtg.).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *K. L. Nichols*
Well Plugging Supervisor

DATE 1-11-72

INV. NO. 4928-W