

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-20034-00-00

JAN 2 1968
1-2-68

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Burch Exploration, Incorporated,

Complete Address 601 Union Center, Wichita, Kansas.

Lease Name Gillespie Well No. 1

Location NE-NW-SW Sec. 27 Twp. 5 Rge. (E) (W) 27

County Decatur Total Depth 3860'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Abercrombie Drilling, Incorporated,

Address 801 Union Center, Wichita, Kansas. License No.

Operation Completed: Hour 10:00 AM Day 30 Month 12 Year 1967

The above well was plugged as follows:

217'--7" OD Surface casing, cement circulated with 115 Sx. (6 1/2" Hole).
Dakota section from 1200' to 1375'.

Circulated hole with heavy mud. Pulled DP to 11400' and displaced 65 Sx. cement thru
DP from 11400' to 1075'. Pulled DP to 240' and displaced 15 Sx. cement thru DP from
240' to 165'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 5 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols
Well Plugging Supervisor

DATE 1-3-68

INV. NO. 7021-W