

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-00580-00-00

RECEIVED  
STATE CORPORATION COMMISSION

JUL 7 1965  
7-7-65  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Continental Oil Company,

Complete Address: Box # 267, Great Bend, Kansas.

Lease Name G. Gillespie Well No. A-2

Location SW-NE-SE Sec. 27 Twp. 5 Rge. (E) (W) 27

County Decatur Total Depth 3720

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Forbes Casing Pulling, Incorporated,

Address: Box # 221, Great Bend, Kansas. License No. 49

Operation Completed: Hour 12:00M Day 1 Month 7 Year 1965

The Above well was plugged as follows:

240'--10 3/4" Surface pipe, cement circulated.

3720'--5 1/2" Production casing. Well Plugged back to 3683'. Top perfor-  
ations @ 3648'.

Sanded well back to 3635' and set 5 Sx. cement with dump bailer. Pulled

5 1/2" to 600' and circulated heavy gel mud, (Used 20 Sx. gel) Pulled 5 1/2"

to 540' and displaced 25 Sx. cement thru 5 1/2". Pulled 5 1/2" to 240' and

displaced 25 Sx. cement thru 5 1/2". Pulled 5 1/2", set rock bridge @ 35' and

15 Sx. cement to bottom of cellar. (Recovered 1230' 5 1/2" casing)

(Mudding and cementing operations performed by Halliburton)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Dechels  
Well Plugging Supervisor

DATE 7/7/65

INV. NO. 1423-W